



Monday, May 1, 2023

**Sweetwater Authority**

**Phone: (925) 681 0220**

**Email: [Carlos.Rivera@sedgwick.com](mailto:Carlos.Rivera@sedgwick.com)**

**Attention: Carlos Rivera**

**Regarding: Loveland Reservoir replacement Aluminum Fishing Dock.**

**ITEM #1;**

**One (2) 8' Wide x 20' Long Aluminum End Fishing Dock, Inc:**

- Aluminum channel frame with aluminum channel center deck stringers.
- Hallsten aluminum decking is ribbed and sandblasted for a nonskid surface.
- 2 rail handrail 34" high on both sides and one end, with curb.
- Cross member under deck for attachment of flotation.
- Flotation for dead loads and minimum 20 lbs./ft<sup>2</sup> live load capacity.
- Galvanized steel tubular dock ends and hinged connections between dock sections.
- (2) Winch stands

**Unit Cost: \$19,889.00 ea.**

**For only: \$39,778.00 ea.**

**ITEM #2;**

**Two (2) 8' Wide x 20' Long Aluminum Middle Fishing Dock, Inc:**

- Aluminum channel frame with aluminum channel center deck stringers.
- Hallsten aluminum decking is ribbed and sandblasted for a nonskid surface.
- 2 rail handrail 34" high on both sides with curb.
- Cross member under deck for attachment of flotation.
- Flotation for dead loads and minimum 20 lbs./ft<sup>2</sup> live load capacity.
- Galvanized steel tubular dock ends and hinged connections between dock sections.

**Unit Cost: \$17,560.00 ea.**

**For only: \$35,120.00 ea.**

**ITEM #3;**

**Four (4) Winches, Cable and Anchor System, Inc:**

- (4) four M452 Thern Winches.
- (2) Two- 300 Lbs. Anchors & Connecting Hardware.
- (4) 250' of length 3/8" S.S. Cable connected to 10' of 1/2" Anchor chain grade 43 for attachment to anchors with double clevis & shackles.

**For only: \$19,820.00 ea.**

**FOB Delivery: \$4,400.00**

**Material Cost: \$99,118.00**  
**7.75% Sales Tax: \$7,681.65**  
**Delivered Material Total: \$106,799.65**



**Including:**

- Shop drawings for approval before fabrication and delivery.
- FOB Delivery to nearest over the road trucks stop to the job site, Loveland Reservoir, CA.

**Exclusions:**

- Repair work or modifications to existing docks.
- Demolition and removal of any existing dock system.
- Prevailing wage/ Certified Payroll (available upon request of additional cost)
- Trash dumpster or facilities.
- Concrete work of any kind is not included.
- Main anchorage cable system of any kind.
- Water supply, piping, conduits, electrical, etc.

**Lead Time:**

Hallsten Corporation has a large amount of work right now and the lead times are greater than usual. Please be patient with our schedules and we will do the best we can for your project. Current lead times;

Drawings: 3-4 weeks, Fabrication: 14-18 weeks, Delivery & Installation: 3-4 weeks.

This modular system can be expanded on very easily. If you have any questions or if you would like to change the details of this quotation, please contact me. If you would like to place an order, please let me know.

Thank you for your inquiry for Hallsten Corporations quality marine products.

Sincerely,

Juan Rodriguez  
Marine Project Manager