

Bid Results

Item #	QUANTITY	UNIT	SDF WELL #11-PURCHASE AND INSTALL VERTICAL TURBINE PUMP	Brax		Layne Christensen		Hydrocurrent	
				Unit	Line Total	Unit	Line Total	Unit	Line Total
1	1	LS	MOBILIZATION AND DEMOBILIZATION	\$ -	\$ -	\$ 13,410.00	\$ 13,410.00	\$ 3,480.00	\$ 3,480.00
2	1	EA	GOULDS 13CHC OR SIMFLO 11H STAINLESS STEEL VERTICAL TURBINE BOWL ASSEMBLY	\$ 42,230.60	\$ 42,230.60	\$ 33,275.00	\$ 33,275.00	\$ 41,580.00	\$ 41,580.00
3	32	EA	PURCHASE AND INSTALL, 316SS - 10" COUPLING WITH PHENOLIC LINING	\$ 1,365.39	\$ 43,692.48	\$ 1,150.00	\$ 36,800.00	\$ 3,179.00	\$ 101,728.00
4	1	EA	CLEAN AND REUSE DISCHARGE HEAD - 10 x 18" NIPPLE PE X BUTT, THREADS SHALL BE CLEANED AND CHASED	\$ 2,120.00	\$ 2,120.00	\$ 650.00	\$ 650.00	\$ 1,280.00	\$ 1,280.00
5	32	EA	PURCHASE AND INSTALL, 304SS SHAFT RETAINER 10"	\$ 299.59	\$ 9,586.88	\$ 240.00	\$ 7,680.00	\$ 753.00	\$ 24,096.00
6	32	EA	PURCHASE AND INSTALL, RUBBER INSERT 1-11/16"	\$ 35.16	\$ 1,125.12	\$ 26.00	\$ 832.00	\$ 84.00	\$ 2,688.00
7	1	LS	PURCHASE AND INSTALL, SHAFT 1 11/16 RD 416SS PSQ (HEAD SHAFT), 77-INCHES LONG	\$ 2,008.69	\$ 2,008.69	\$ 910.00	\$ 910.00	\$ 2,765.00	\$ 2,765.00
8	1	LS	MISCELLANEOUS CONSUMABLES	\$ 1,395.00	\$ 1,395.00	\$ 970.00	\$ 970.00	\$ 840.00	\$ 840.00
9	1	LS	RECONDITION MECHANICAL SEAL AND SEAL GLAND	\$ 1,279.00	\$ 1,279.00	\$ 1,550.00	\$ 1,550.00	\$ 2,350.00	\$ 2,350.00
10	18	EA	CUT, THREAD AND STRAIGHTEN EXISTING SHAFTS, THREADS SHALL BE PHENOLIC LINED	\$ 618.88	\$ 11,139.84	\$ 445.00	\$ 8,010.00	\$ 232.00	\$ 4,176.00
11	18	EA	CUT, THREAD AND STRAIGHTEN EXISTING COLUMN PIPE, THREADS SHALL BE PHENOLIC LINED	\$ 1,302.37	\$ 23,442.66	\$ 1,200.00	\$ 21,600.00	\$ 1,154.00	\$ 20,772.00
13	1	LS	LABOR TO COMPLETE WORK DETAILED IN SCOPE OF WORK	\$ 28,582.00	\$ 28,582.00	\$ 26,382.05	\$ 26,382.05	\$ 6,400.00	\$ 6,400.00
					\$ 166,602.27		\$ 152,069.05		\$ 212,155.00